

Project Details

PROJECT NAME	Dutton Park Station
PROJECT LOCATION	Dutton Park, Brisbane
CASA ROLE	Structural Steel subcontractor
CLIENT	Queensland Rail
CONTRACT VALUE	\$3,600,000
PROJECT COMPLETION DATE	May 2024
CONSTRUCTION MANAGER	Peter Casa
PROJECT MANAGER/CONTRACT ADMINISTRATOR	Karl Vogt
SITE SUPERVISOR/SITE MANAGER	Michael Major

Project Scope

CASA engaged to supply and install platform structures as part of the Dutton Park station relocation. Structures included a 50m cranked footbridge, bridge support column, canopies and stair towers. The footbridge required off site preassembly of the structure and partial fitout to reduce the disruption to local roads and rail services.

Key points

- Works completed in suburban Brisbane
- Works fabricated to MRTS78 specification
- Installation occurred during weekend closure of rail and local roads
- Footbridge made up of three sections which was fitted out prior to lifting into position
- Footbridge installed without the need for temporary works, therefore reducing the rail closure time

